

**AMENDMENT OF CLAIMS**

1-25. cancelled

26. (currently amended) A method of manually installing a string of arch shape cross section leaching chambers having sidewalls with a multiplicity of perforations for passage of water, for forming an interconnected string of chambers within a trench in soil; wherein the trench defines the path of said string and has a width sufficient to receive only a single string of chambers connected end-to-end, wherein each chamber has a first end and an opposing second end; wherein the first and second ends of adjacent chambers of the string connect with a load transferring joint; which method comprises the steps of (a) lifting removing a first chamber from the top of a stack of nested chambers; (b) placing the first chamber in said trench; (c) removing a second chamber from the top of a stack of nested chambers; (d) engaging the first end of the second chamber with the second end of the first chamber by vertically angling the second chamber relative to the first chamber and then lowering the second end of the second chamber into the trench to thereby form said joint between said chambers; wherein the person doing the manual installing stands in the trench and manipulates the second chamber during step (d); wherein the length of each chamber is in at least 4 feet and no greater than the range of 4 feet to 5.7 feet; and wherein each chamber has a flexibility factor of greater than about 0.2 inch.

27. (currently amended) The method of claim 26 wherein the lifting step is performed by a single person grasping opposing ends of the chamber. said joint between two mating chambers provides an essentially linear connection so said string lies along a straight line.

28. cancelled.

29. (previously presented) The method of claim 26 wherein the length of each chamber is between about 4 and 5 feet.

30. cancelled

31. (currently amended) The method of claim 2630 wherein each chamber has a flexibility factor of greater than about one inch.

32. (currently amended) The method of claim 26 wherein each chamber has a length to width aspect ratio between about 1.2 and 2.0, a weight per foot of about 2.7 to 3 pounds, and a flexibility factor of greater than about 0.2 inch.

33. (currently amended) The method of claim 26 wherein each chamber comprises a continuous curve arch shape cross section; and wherein the interior and exterior surfaces are substantially free of ribs; and wherein each chamber has a length to width aspect ratio between 1.2 and 2.0, a weight per foot of about 2.7 to 3 pounds.

34. cancelled

35. cancelled

36. (currently amended) An arch shape cross section molded thermoplastic leaching chamber comprising: a first end and a second end; opposing sidewalls with a multiplicity of horizontal slot perforations for passage of water; a length at least 4 feet and no greater than 5.7 feet in the range of about 4 to about 5 feet; a length to width aspect ratio between 1.2 and 2.0; a weight per foot of about 2.7 to 3 pounds; and, a flexibility factor of greater than about 0.2 inch; wherein, a first end of the chamber resists removal from the top of a nested vertical stack of like chambers when only the second end of the chamber is lifted from the stack.

37. (previously presented) The chamber of claim 36 having a width of about 3 feet.

38. (currently amended) The chamber of claim 36 wherein the flexibility factor is at least greater than about 1 inch.

39. (currently amended) A continuous curve arch shape cross section molded thermoplastic corrugated leaching chamber which comprises: interior and exterior surfaces which are substantially free of ribs; opposing sidewalls having a multiplicity of horizontal slot perforations; and, opposing first and second ends shaped for interconnecting with like chambers; wherein the chamber has a flexibility factor of at least 0.2 inch; wherein the chamber has a length at least 4 feet and no greater than 5.7 feet in the range 4 to 5.7 feet; and, wherein the first end of the chamber resists removal from a nested vertical stack of like chambers when only the second end of the chamber is lifted from the stack.

40. (previously presented) The chamber of claim 39 wherein the flexibility factor is at least 1 inch.